

## Kismet Hybrid Rocket Engine Cold Flow 6

Cold Flow Test Operations Procedures

## **Cold Flow Test Operations Procedures**

☐ Control System Operator [CONTROL]

☐ Heating Technician [HEAT]

□ Perimeter Guard 1 [P1]

☐ Perimeter Guard 2 [P2]

□ Perimeter Guard 3 [P3]

5

6

7

8

Contents
This document contains the following procedure:
• The <i>Cold Flow Test</i> procedure comprises steps for conducting a carbon dioxide test of the engine and fill system using the electrical control system and motorized ball valves.
Personnel Required
The test operations team consists of nine personnel:
$\Box$ The <b>Operations Director [OPS]</b> directs operations procedures and communicates with the other test personnel.
$\Box$ The <b>Primary Fill Operator [PRIMARY]</b> is the main system operator. <b>PRIMARY</b> operates all manual valves as well as the test control system.
☐ The <b>Secondary Fill Operator [SECONDARY]</b> is the backup for <b>PRIMARY</b> , and communicates with OPS. If <b>PRIMARY</b> becomes incapacitated, <b>SECONDARY</b> is responsible for removing them from danger.
$\ \square$ The DAQ Technician [DAQ] monitors and operates the test data acquisition system.
☐ the Control System Operator [CONTROL] operates the test control system, including actuation of remote valves.
$\Box$ The <b>Heating Technician [HEAT]</b> operates the valves for the tank heating system.
□ Perimeter Guard 1 [P1], Perimeter Guard 2 [P2], and Perimeter Guard 3 [P3] ensure that no unauthorized personnel enter the testing area during test operations.
Sign-Off
To be completed by all test personnel after reading and familiarization with procedures
□ Operations Director [OPS]
□ Primary Fill Operator [PRIMARY]
□ Secondary Fill Operator [SECONDARY]
□ DAQ Technician [DAQ]

## Prior to Start

1	$\square$ Ensure that the following procedures are complete:
2	☐ Oxidizer Tank Assembly procedure
3	☐ Plumbing Setup procedure
4	☐ Oxidizer Tank Stand Setup procedure
5	$\square$ Tank Heating Setup procedure
6	$\square$ Test Stand Setup procedure
7	$\square$ Data Acquisition Setup procedure
8	☐ Test Control System Setup procedure
9	$\Box$ Ensure that all technicians as defined above are available and have completed the sign-off.
10	$\square$ Ensure that all spectators and test personnel are wearing safety glasses.
11	☐ Ensure that <b>PRIMARY</b> and <b>SECONDARY</b> are wearing face shields and have no exposed skin.
12	☐ Ensure that <b>PRIMARY</b> is wearing thermal gloves.
13	☐ Ensure that <b>OPS</b> is in possession of the system control key.

## Cold Flow Test Procedure

1	□ <b>OPS</b> : Confirm that the camera equipment is set up.
2	□ PRIMARY: Confirm that the following valves are initially closed:
3	☐ Cylinder Valve
4	☐ Remote Fill Valve
5	□ Parallel Fill Valve
6 7	☐ Motorized Vent Valve
	☐ Injector Valve
8	□ PRIMARY: Confirm that the following valves are initially open:
9	☐ Series Fill Valve
10	□ DAQ: Confirm that all pressure transducers are reading atmospheric pressure.
11	□ DAQ: Confirm that all load cells are reading the determined zero point.
12	□ PAUSE POINT
13	□ P1, P2, and P3: Close the perimeter and do not allow any further personnel to enter the testing area.
14	□ SECONDARY: Confirm that no personnel are present in the testing area other than PRIMARY and SECONDARY.
15	☐ PRIMARY: Remove the cap from the carbon dioxide supply cylinder.
16	□ <b>PRIMARY</b> : Connect the fill line to the supply cylinder, hand tighten, and then tighten with a wrench. Do not force the connection.
17	$\Box$ <b>PRIMARY</b> : Slowly open the Cylinder Valve through $\frac{3}{4}$ of a turn.
	• If leaks are observed:
18	□ PRIMARY: Close the Cylinder Valve.
19	□ PRIMARY: Slowly open the Parallel Fill Valve.
20 21	<ul> <li>DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.</li> <li>OPS: Abort test procedures and revisit plumbing setup.</li> </ul>
22	□ PRIMARY: Communicate the supply cylinder pressure as visible on the Pressure Gauge.
23	□ DAQ: Communicate the supply cylinder pressure as read by the Fill Pressure Transducer.
24	□ DAQ: Confirm that the two pressure measurements are in agreement.
25	☐ PRIMARY and SECONDARY: Retreat back to Mission Control.
26	□ CONTROL: Perform the following control system checks:
27	☐ Confirm that all actuator controls are in the "closed" position:
28	☐ Remote Fill Valve
29	☐ Motorized Vent Valve
30	□ PAUSE POINT
31	$\square$ OPS: Poll the following personnel for GO/NO GO status:
32	□ HEAT
33	□ CONTROL

34	□ DAQ
35	□ PRIMARY
36	□ SECONDARY
37	□ <b>P1</b>
38	□ <b>P2</b>
39	□ <b>P3</b>
40	□ <b>OPS</b> : Give the system control key to <b>CONTROL</b> .
41	□ CONTROL: Engage the key switch and power on the control boxes.
42	□ CONTROL: Open the Motorized Vent Valve.
43	□ CONTROL: Open the Remote Fill Valve.
	• If leaks are observed:
44	□ CONTROL: Close the Remote Fill Valve.
45	□ PRIMARY: Open the Injector Valve.
46	□ OPS: Proceed only when the oxidizer tank has fully vented.
47 48	<ul> <li>PRIMARY: Close the Cylinder Valve.</li> <li>DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.</li> </ul>
49	□ OPS: Abort test procedures and revisit plumbing setup.
50	$\square$ <b>OPS</b> : Proceed only when a white plume is visible from the vent plug.
51	□ CONTROL: Close the Motorized Vent Valve.
52	□ CONTROL: Close the Remote Fill Valve.
53	☐ <b>HEAT</b> : Open the Tank Heating Valve.
54	☐ DAQ: Proceed only when the oxidizer tank pressure is at least 750 psi.
	• If the oxidizer tank pressure does not reach 750 psi:
55	☐ HEAT: Close the Tank Heating Valve.
56	□ PRIMARY: Open the Injector Valve.
57	OPS: Proceed only when the oxidizer tank has fully vented.
58 59	<ul> <li>PRIMARY and SECONDARY: Approach the test plumbing.</li> <li>PRIMARY: Close the Cylinder Valve.</li> </ul>
60	□ CONTROL: Open the Remote Fill Valve.
61	□ DAQ: Confirm that the Oxidizer Tank Pressure Transducer is reading atmospheric pressure.
62	□ OPS: Abort test procedures and revisit plumbing setup.
63	☐ <b>HEAT</b> : Close the Tank Heating Valve.
64	□ PAUSE POINT
65	☐ PRIMARY: Conduct the cold flow test by opening the Injector Valve.
66	□ PAUSE POINT
67	□ DAQ: Confirm that the Oxidizer Tank Pressure Transducer is reading atmospheric pressure.
68	□ CONTROL: Open the Motorized Vent Valve.
69	□ <b>OPS</b> : Proceed only when the oxidizer tank has fully vented.

70	□ PRIMARY and SECONDARY: Approach the test plumbing.
71	□ PRIMARY: Close the Cylinder Valve.
72	□ PRIMARY: Slowly open the Parallel Fill Valve.
73	□ CONTROL: Open the Remote Fill Valve.
74	□ PRIMARY: Disconnect the fill line from the supply cylinder.
75	☐ PRIMARY: Replace the cap on the carbon dioxide supply cylinder.
76	$\hfill \square$ DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure
77	□ <b>OPS</b> : Wait for at least 3 minutes before proceeding.
78	□ P1, P2, and P3: Open the perimeter.

□ **OPS**: Proceed with teardown and disassembly.

79