

## UXO Hybrid Rocket Engine Cold Flow 1

Cold Flow Test Operations Procedures

## **Cold Flow Test Operations Procedure**

_	•	_			_		٠.	
l	١.(	ገ	n	т	e	n	†9	5

This document contains two procedures:

- The Cold Flow Test Remote Control procedure comprises steps for operating the fill system using the electrical control system and motorized ball valves.
- The Cold Flow Test Manual Control procedure comprises steps for operating the fill system using manually

	operated ball valves.	comprises steps for operating the fill system using manually		
	Personnel Required			
	The test operations team consists of seven personnel:			
1	☐ The <b>Operations Director [OPS]</b> directs opera personnel.	tions procedures and communicates with the other test		
2	☐ The <b>Primary Fill Operator [PRIMARY]</b> is the valves as well as the test control system.	e main system operator. PRIMARY operates all manual		
3	☐ The Secondary Fill Operator [SECONDARY] is the backup for PRIMARY, and communicates with OPS. If PRIMARY becomes incapacitated, SECONDARY is responsible for removing them from danger.			
4	☐ The DAQ Technician [DAQ] monitors and operates the test data acquisition system.			
5	☐ The <b>Heating Technician [HEAT]</b> operates the v	valves for the tank heating system.		
5	☐ Perimeter Guard 1 [P1] and Perimeter Guard testing area during test operations.	1 2 [P2] ensure that no unauthorized personnel enter the		
	Sign-Off			
	To be completed by all test personnel after reading an	d familiarization with procedures		
L	□ Operations Director [OPS]			
)	☐ Primary Fill Operator [PRIMARY]			
}	☐ Secondary Fill Operator [SECONDARY]			
1	□ DAQ Technician [DAQ]			
)	☐ Heating Technician [HEAT]			
ō	☐ Perimeter Guard 1 [P1]			
7	☐ Perimeter Guard 2 [P2]			

## Prior to Start

1	$\square$ Ensure that the following procedures are complete:
2	☐ Oxidizer Tank Assembly procedure
3	☐ Plumbing Setup procedure
4	☐ Oxidizer Tank Stand Setup procedure
5	☐ Tank Heating Setup procedure
6	$\square$ Test Stand Setup procedure
7	$\square$ Data Acquisition Setup procedure
8	$\square$ Test Control System Setup procedure
9	$\hfill\Box$ Ensure that all technicians as defined above are available and have completed the sign-off.
10	$\hfill\Box$ Ensure that the following personnel have walkie-talkies and communication is functional:
11	□ OPS
12	□ SECONDARY
13	□ DAQ
14	□ HEAT
15	□ <b>P1</b>
16	□ <b>P2</b>
17	$\square$ Ensure that all spectators and test personnel are wearing safety glasses.
18	☐ Ensure that PRIMARY and SECONDARY are wearing face shields and have no exposed skin.
19	☐ Ensure that <b>PRIMARY</b> is wearing thermal gloves.
20	☐ Ensure that <b>SECONDARY</b> is in possession of the system control key.

## Cold Flow Test - Remote Control Procedure

1	□ PRIMARY: Confirm that the following valves are initially closed:
2	☐ Remote Fill Valve
3	☐ Parallel Fill Valve
4	☐ Line Vent Valve
5	☐ Cylinder Valve
6	☐ Pressure Relief Valve
7	☐ Shutoff Valve
8	□ PRIMARY: Confirm that the following valves are initially open:
9	<ul><li>□ Tank Vent Valve</li><li>□ Series Fill Valve</li></ul>
11	□ DAQ: Confirm that all pressure transducers are reading atmospheric pressure.
12	□ DAQ: Confirm that all load cells are reading the determined zero point.
13	□ PAUSE POINT
14	□ P1 and P2: Close the perimeter and do not allow any further personnel to enter the testing area.
15	□ SECONDARY: Confirm that no personnel are present in the testing area other than PRIMARY and SECONDARY.
16	☐ PRIMARY: Remove the cap from the carbon dioxide supply cylinder.
17	$\Box$ <b>PRIMARY</b> : Connect the fill line to the supply cylinder, hand tighten, and then tighten with a wrench. Do not force the connection.
18	□ PRIMARY: Slowly open the Cylinder Valve through of a turn.
	• If leaks are observed:
19	☐ PRIMARY: Close the Cylinder Valve.
20	□ PRIMARY: Slowly open the Line Vent Valve.
21 22	<ul><li>PRIMARY: Slowly open the Parallel Fill Valve.</li><li>DAQ: Confirm that the fill lines are fully depressurized.</li></ul>
23	□ OPS: Abort test procedures and revisit plumbing setup.
24	☐ PRIMARY: Communicate the supply cylinder pressure as visible on the Pressure Gauge.
25	□ DAQ: Communicate the supply cylinder pressure as read by the Fill Pressure Transducer.
26	□ DAQ: Confirm that the two pressure measurements are in agreement.
27	☐ PRIMARY and SECONDARY: Retreat to the test control area, behind the blast shield.
28	□ PRIMARY: Perform the following control system checks:
29	$\square$ Confirm that all actuator controls are in the "off" position:
30	<ul><li>☐ Remote Fill Valve</li><li>☐ Tank Vent Valve</li></ul>
31	
32	□ PAUSE POINT
33	□ OPS: Poll the following personnel for GO/NO GO status:

34	□ <b>P1</b>
35	□ <b>P2</b>
36	□ <b>HEAT</b>
37	□ DAQ
38	□ PRIMARY
39	□ SECONDARY
40	☐ SECONDARY: Give the system control key to PRIMARY.
41	□ PRIMARY: Engage the key switch and power on the control boxes.
42	□ PRIMARY: Open the Remote Fill Valve.
	• If leaks are observed:
43	☐ PRIMARY: Close the Remote Fill Valve.
44	☐ PRIMARY: Open the Line Vent Valve using the ropes.
45	☐ SECONDARY: Proceed only when the oxidizer tank has fully vented.
46	☐ PRIMARY and SECONDARY: Approach the test plumbing.
47	☐ PRIMARY: Close the Cylinder Valve.
48	☐ PRIMARY: Open the Remote Fill Valve.
49	<ul> <li>DAQ: Confirm that the fill lines are fully depressurized.</li> </ul>
50	□ <b>OPS</b> : Abort test procedures and revisit plumbing setup.
	If the Remote Fill Valve fails to open:
51	□ <b>OPS</b> : Proceed to the Manual Control procedure.
52	□ DAQ: Wait until the oxidizer tank mass plateaus.
53	□ PRIMARY: Close the Remote Fill Valve.
	If the Remote Fill Valve fails to close:
54	☐ PRIMARY and SECONDARY: Approach the test plumbing.
55	☐ PRIMARY: Close the Series Fill Valve.
56	☐ PRIMARY and SECONDARY: Retreat to the test control area, behind the blast shield.
57	□ PRIMARY: Close the Tank Vent Valve.
58	☐ <b>HEAT</b> : Open the Tank Heating Valve.
59	□ DAQ: Proceed only when the oxidizer tank pressure is at least 650 psi.
	• If the oxidizer tank pressure does not reach 650 psi:
60	☐ <b>HEAT</b> : Close the Tank Heating Valve.
61	☐ PRIMARY: Open the Line Vent Valve using the ropes.
62	☐ SECONDARY: Proceed only when the oxidizer tank has fully vented.
63	☐ PRIMARY and SECONDARY: Approach the test plumbing.
64	☐ PRIMARY: Close the Cylinder Valve.
65	☐ PRIMARY: Slowly open the Remote Fill Valve.
66	□ DAQ: Confirm that the fill lines are fully depressurized.
67	□ <b>OPS</b> : Abort test procedures and revisit plumbing setup.
68	☐ <b>HEAT</b> : Close the Tank Heating Valve.
69	□ PAUSE POINT

70	☐ PRIMARY: Conduct the cold flow test by opening the Shutoff Valve using the ropes.
71	□ PAUSE POINT
72	□ <b>OPS</b> : Wait for at least 3 minutes before proceeding.
73	□ PRIMARY: Open the Line Vent Valve using the ropes.
74	□ PRIMARY and SECONDARY: Approach the test plumbing.
75	□ PRIMARY: Close the Cylinder Valve.
76	□ PRIMARY: Open the Remote Fill Valve.
77	□ DAQ: Confirm that all pressure transducers are reading atmospheric pressure.
78	□ <b>OPS</b> : Wait for at least 3 minutes before proceeding.
79	□ P1 and P2: Open the perimeter.
80	□ <b>OPS</b> : Proceed with teardown and disassembly.