

Kismet Hybrid Rocket Engine Cold Flow 5

Cold Flow Test Operations Procedures

Cold Flow Test Operations Procedures

☐ Control System Operator [CONTROL]

☐ Heating Technician [HEAT]

□ Perimeter Guard 1 [P1]

☐ Perimeter Guard 2 [P2]

□ Perimeter Guard 3 [P3]

5

6

7

8

Contents
This document contains the following procedure:
• The <i>Cold Flow Test</i> procedure comprises steps for conducting a carbon dioxide test of the engine and fill system using the electrical control system and motorized ball valves.
Personnel Required
The test operations team consists of nine personnel:
\Box The Operations Director [OPS] directs operations procedures and communicates with the other test personnel.
\Box The Primary Fill Operator [PRIMARY] is the main system operator. PRIMARY operates all manual valves as well as the test control system.
☐ The Secondary Fill Operator [SECONDARY] is the backup for PRIMARY , and communicates with OPS. If PRIMARY becomes incapacitated, SECONDARY is responsible for removing them from danger.
$\ \square$ The DAQ Technician [DAQ] monitors and operates the test data acquisition system.
☐ the Control System Operator [CONTROL] operates the test control system, including actuation of remote valves.
\Box The Heating Technician [HEAT] operates the valves for the tank heating system.
□ Perimeter Guard 1 [P1], Perimeter Guard 2 [P2], and Perimeter Guard 3 [P3] ensure that no unauthorized personnel enter the testing area during test operations.
Sign-Off
To be completed by all test personnel after reading and familiarization with procedures
□ Operations Director [OPS]
□ Primary Fill Operator [PRIMARY]
□ Secondary Fill Operator [SECONDARY]
□ DAQ Technician [DAQ]

Prior to Start

1	\square Ensure that the following procedures are complete:
2	☐ Oxidizer Tank Assembly procedure
3	☐ Plumbing Setup procedure
4	☐ Oxidizer Tank Stand Setup procedure
5	\square Tank Heating Setup procedure
6	\square Test Stand Setup procedure
7	\square Data Acquisition Setup procedure
8	☐ Test Control System Setup procedure
9	\Box Ensure that all technicians as defined above are available and have completed the sign-off.
10	\square Ensure that all spectators and test personnel are wearing safety glasses.
11	☐ Ensure that PRIMARY and SECONDARY are wearing face shields and have no exposed skin.
12	☐ Ensure that PRIMARY is wearing thermal gloves.
13	☐ Ensure that OPS is in possession of the system control key.

Cold Flow Test Procedure

1	□ PRIMARY: Confirm that the following valves are initially closed:
2	☐ Cylinder Valve
3	☐ Remote Fill Valve
4	☐ Parallel Fill Valve
5	☐ Motorized Vent Valve
6	☐ Line Vent Valve
7	☐ Injector Valve
8	□ PRIMARY: Confirm that the following valves are initially open:
9	☐ Series Fill Valve
10	□ DAQ: Confirm that all pressure transducers are reading atmospheric pressure.
11	□ DAQ: Confirm that all load cells are reading the determined zero point.
12	□ PAUSE POINT
13	□ P1, P2, and P3: Close the perimeter and do not allow any further personnel to enter the testing area.
14	□ SECONDARY: Confirm that no personnel are present in the testing area other than PRIMARY and SECONDARY.
15	☐ PRIMARY: Remove the cap from the carbon dioxide supply cylinder.
16	\Box PRIMARY : Connect the fill line to the supply cylinder, hand tighten, and then tighten with a wrench. Do not force the connection.
17	\Box PRIMARY : Slowly open the Cylinder Valve through $\frac{3}{4}$ of a turn.
	• If leaks are observed:
18	☐ PRIMARY: Close the Cylinder Valve.
19	□ PRIMARY: Open the Line Vent Valve.
20 21	 PRIMARY: Slowly open the Parallel Fill Valve. DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.
22	□ OPS: Abort test procedures and revisit plumbing setup.
23	☐ PRIMARY: Communicate the supply cylinder pressure as visible on the Pressure Gauge.
24	□ DAQ: Communicate the supply cylinder pressure as read by the Fill Pressure Transducer.
25	□ DAQ: Confirm that the two pressure measurements are in agreement.
26	☐ PRIMARY and SECONDARY: Retreat back to Mission Control.
27	□ CONTROL: Perform the following control system checks:
28	\square Confirm that all actuator controls are in the "closed" position:
29	☐ Remote Fill Valve
30	☐ Motorized Vent Valve
31	☐ Injector Valve
32	□ PAUSE POINT
33	□ OPS: Poll the following personnel for GO/NO GO status:

34	□ HEAT
35	□ CONTROL
36	□ DAQ
37	□ PRIMARY
38	□ SECONDARY
39	□ P1
40	□ P2
41	□ P3
42	□ OPS: Give the system control key to CONTROL.
43	□ CONTROL: Engage the key switch and power on the control boxes.
44	□ CONTROL: Open the Motorized Vent Valve.
45	□ CONTROL: Open the Remote Fill Valve.
	• If leaks are observed:
46	□ CONTROL: Close the Remote Fill Valve.
47	□ CONTROL: Open the Injector Valve.
48	OPS: Proceed only when the oxidizer tank has fully vented.
49 50	□ PRIMARY: Close the Cylinder Valve.
51	 DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure. OPS: Abort test procedures and revisit plumbing setup.
52	□ OPS : Proceed only when a white plume is visible from the vent plug.
53	□ CONTROL: Close the Motorized Vent Valve.
54	□ CONTROL: Close the Remote Fill Valve.
55	☐ HEAT : Open the Tank Heating Valve.
56	□ DAQ: Proceed only when the oxidizer tank pressure is at least 750 psi.
	• If the oxidizer tank pressure does not reach 750 psi:
57	☐ HEAT : Close the Tank Heating Valve.
58	☐ CONTROL: Open the Injector Valve.
59	OPS: Proceed only when the oxidizer tank has fully vented.
60	□ PRIMARY and SECONDARY: Approach the test plumbing.
61 62	□ PRIMARY: Close the Cylinder Valve.□ CONTROL: Open the Remote Fill Valve.
63	 □ DAQ: Confirm that the Oxidizer Tank Pressure Transducer is reading atmospheric pressure.
64	□ OPS : Abort test procedures and revisit plumbing setup.
65	☐ HEAT : Close the Tank Heating Valve.
66	□ PAUSE POINT
67	□ CONTROL: Conduct the cold flow test by opening the Injector Valve.
68	□ PAUSE POINT
69	□ DAQ: Confirm that the Oxidizer Tank Pressure Transducer is reading atmospheric pressure.

70	□ PRIMARY: Open the Line Vent Valve using the ropes.
71	□ CONTROL: Open the Motorized Vent Valve.
72	\square OPS : Proceed only when the oxidizer tank has fully vented.
73	☐ PRIMARY and SECONDARY: Approach the test plumbing.
74	□ PRIMARY: Close the Cylinder Valve.
75	□ PRIMARY: Slowly open the Parallel Fill Valve.
76	□ CONTROL: Open the Remote Fill Valve.
77	□ PRIMARY: Disconnect the fill line from the supply cylinder.
78	☐ PRIMARY: Replace the cap on the carbon dioxide supply cylinder.
79	$\ \square$ DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.
80	\square OPS : Wait for at least 3 minutes before proceeding.
81	□ P1, P2, and P3: Open the perimeter.

□ **OPS**: Proceed with teardown and disassembly.

82