

Unnamed Liquid Rocket Engine Cold Flow 1

Cold Flow Test Operations Procedures

Cold Flow Test Operations Procedures

Contents
This document contains the following procedure:
• The <i>Cold Flow Test</i> procedure comprises steps for conducting a cold flow test of the engine and fill system using the electrical control system and motorized ball valves.
Personnel Required
The test operations team consists of nine personnel:
\Box The Operations Director [OPS] directs operations procedures and communicates with the other test personnel.
\Box The Primary Fill Operator [PRIMARY] is the main system operator. PRIMARY operates all manual valves as well as the test control system.
☐ The Secondary Fill Operator [SECONDARY] is the backup for PRIMARY, and communicates with OPS. If PRIMARY becomes incapacitated, SECONDARY is responsible for removing them from danger.
☐ The DAQ Technician [DAQ] monitors and operates the test data acquisition system.
\Box The Control System Operator [CONTROL] operates the test control system, including actuation of remote valves.
□ Perimeter Guard 1 [P1], Perimeter Guard 2 [P2], and Perimeter Guard 3 [P3] ensure that no unauthorized personnel enter the testing area during test operations.
Background Information
All personnel should familiarize themselves with the following information prior to test start:
 All electrically actuated valves have two names: an alphanumeric code used in the plumbing master system, and a descriptive name used in control system code and documentation. For this test, the correspondence is as follows:
- MV-1 is the Remote Fill Valve
MV-2 is the Pressurant Valve
MV-3 is the Motorized Vent Valve
Sign-Off
To be completed by all test personnel after reading and familiarization with procedures
□ Operations Director [OPS]
□ Primary Fill Operator [PRIMARY]
□ Secondary Fill Operator [SECONDARY]
□ DAQ Technician [DAQ]
□ Control System Operator [CONTROL]
□ Perimeter Guard 1 [P1]
□ Perimeter Guard 2 [P2]
□ Perimeter Guard 3 [P3]

Prior to Start

1	\square Ensure that the following procedures are complete:
2	☐ Oxidizer Tank Assembly procedure
3	☐ Plumbing Setup procedure
4	☐ Oxidizer Tank Stand Setup procedure
5	\square Tank Heating Setup procedure
6	\square Test Stand Setup procedure
7	\square Data Acquisition Setup procedure
8	☐ Test Control System Setup procedure
9	\Box Ensure that all technicians as defined above are available and have completed the sign-off.
10	\square Ensure that all spectators and test personnel are wearing safety glasses.
11	☐ Ensure that PRIMARY and SECONDARY are wearing face shields and have no exposed skin.
12	☐ Ensure that PRIMARY is wearing thermal gloves.
13	☐ Ensure that OPS is in possession of the system control key.

Cold Flow Test Procedure

1	□ PRIMARY: Confirm that the following valves are initially closed:
2	□ BA-1
3	□ BA-3
4	□ BA-5
5	□ BA-6
6 7	□ BA-9 □ MV-1
8	□ MV-2
9	□ MV-3
10	□ PRIMARY: Confirm that the following valves are initially open:
11	□ BA-2
12	□ BA-4
13	\square DAQ: Confirm that all pressure transducers are reading atmospheric pressure.
14	\square DAQ: Confirm that all load cells are reading the determined zero point.
15	□ PAUSE POINT
16	□ P1, P2, and P3: Close the perimeter and do not allow any further personnel to enter the testing area.
17	□ SECONDARY: Confirm that no personnel are present in the testing area other than PRIMARY and SECONDARY.
18	\square PRIMARY : Slowly open GA-1 through $\frac{3}{4}$ of a turn.
	• If leaks are observed:
19	□ PRIMARY: Close GA-1.
20	□ PRIMARY: TODO
21	□ PRIMARY: Adjust CV-4 to 360 psi.
22	□ DAQ: Communicate the pressure reading of PT-1.
23	□ OPS : Record the pressure reading of PT-1.
24	□ PRIMARY: Communicate the pressure readings of PI-3 and PI-4.
25	□ OPS : Record the pressure readings of PI-3 and PI-4.
26	☐ PRIMARY and SECONDARY: Retreat back to Mission Control.
27	□ CONTROL: Perform the following control system checks:
28	\square Confirm that all actuator controls are in the "closed" position:
29	☐ Remote Fill Valve
30	☐ Motorized Vent Valve☐ Pressurant Valve
31	
32	□ PAUSE POINT
33	DPS: Poll the following personnel for CO/NO CO status:

34	□ CONTROL
35	□ DAQ
36	□ PRIMARY
37	□ SECONDARY
38 39	□ P1 □ P2
40	□ P3
41	□ OPS: Give the system control key to CONTROL.
42	□ CONTROL: Engage the key switch and power on the control boxes.
43	□ CONTROL: Open the Pressurant Valve.
44	\square DAQ: Monitor PT-1 and the fuel tank load cell during fuel pressurization.
45	□ DAQ: Proceed when the fuel tank mass is stable.
46	□ PAUSE POINT
47	□ PRIMARY: Conduct the cold flow test by opening BA-9 using the ropes.
48	\square OPS: Proceed when water flow has ceased or after 15 seconds have elapsed.
49	□ CONTROL: Close the Pressurant Valve.
50	□ PAUSE POINT
51	□ DAQ: Confirm that PT-1 is reading atmospheric pressure.
52	□ CONTROL: Disengage the key switch and disable actuators.
53	□ PRIMARY and SECONDARY: Approach the test plumbing.
54	□ PRIMARY: Close BA-2.
55	□ PRIMARY: Open BA-1.
56	□ PRIMARY: Adjust CV-4 to 600 psi.
57	□ PRIMARY : Disconnect the pressure relief valve assembly from the fuel plumbing and connect it to the oxidizer plumbing.
58	□ DAQ: Communicate the pressure reading of PT-1.
59	□ OPS : Record the pressure reading of PT-1.
60	□ PRIMARY: Communicate the pressure readings of PI-3 and PI-4.
61	□ OPS : Record the pressure readings of PI-3 and PI-4.
62	□ PRIMARY: Remove the cap from SC-1.
63	□ PRIMARY : Connect the fill line to SC-1, hand tighten, and then tighten with a wrench. Do not force the connection.
64	\square PRIMARY : Slowly open the Cylinder Valve through $\frac{3}{4}$ of a turn.
	• If leaks are observed:
65	□ PRIMARY: Close the Cylinder Valve.
66	□ PRIMARY: Slowly open BA-3.

67	□ PRIMARY: Slowly open BA-5.
68 69	DAQ: Confirm that PT-2 is reading atmospheric pressure.OPS: Abort test procedures and revisit plumbing setup.
70	□ PRIMARY: Communicate the reading of PI-2.
71	□ DAQ: Communicate the reading of PT-2.
72	□ DAQ: Confirm that the two pressure measurements are in agreement.
73	☐ PRIMARY and SECONDARY: Retreat back to Mission Control.
74	□ CONTROL: Perform the following control system checks:
75	☐ Confirm that all actuator controls are in the "closed" position:
76	☐ Remote Fill Valve
77	☐ Motorized Vent Valve
78	□ Pressurant Valve
79	□ PAUSE POINT
80	□ OPS: Give the system control key to CONTROL.
81	□ CONTROL: Engage the key switch and power on the control boxes.
82	□ CONTROL: Open the Motorized Vent Valve.
83	□ CONTROL: Open the Remote Fill Valve.
	• If leaks are observed:
84	□ CONTROL: Close the Remote Fill Valve.
85 86	PRIMARY: Open BA-6 using the ropes.OPS: Proceed only when the oxidizer tank has fully vented.
87	☐ PRIMARY: Close the Cylinder Valve.
88	□ DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.
89	□ OPS: Abort test procedures and revisit plumbing setup.
90	□ OPS: Proceed only when a white plume is visible from the vent plug.
91	□ CONTROL: Close the Motorized Vent Valve.
92	□ CONTROL: Close the Remote Fill Valve.
93	□ CONTROL: Open the Pressurant Valve.
94	□ DAQ: Proceed when PT-1 is stable at 600 psi.
95	□ PAUSE POINT
96	□ PRIMARY : Conduct the cold flow test by opening BA-6 using the ropes.
97	\square OPS: Proceed when carbon dioxide flow has ceased or after 15 seconds have elapsed.
98	□ CONTROL: Close the Pressurant Valve.
99	□ PAUSE POINT
100	\square OPS : Proceed only when the oxidizer tank has fully vented.
101	□ DAQ: Confirm that PT-1 is reading atmospheric pressure.

102 ☐ **CONTROL**: Open the Motorized Vent Valve. 103 ☐ PRIMARY and SECONDARY: Approach the test plumbing. 104 ☐ **PRIMARY**: Close the Cylinder Valve. 105 ☐ **PRIMARY**: Slowly open BA-3. ☐ **CONTROL**: Open the Remote Fill Valve. 106 107 ☐ **PRIMARY**: Close GA-1. 108 ☐ **CONTROL**: Open MV-2. 109 ☐ **PRIMARY**: Slowly open BA-2. ☐ **PRIMARY**: Slowly open BA-5. 110 111 ☐ **PRIMARY**: Disconnect the fill line from SC-1. 112 \square **PRIMARY**: Replace the cap on SC-1. 113 □ DAQ: Confirm that all pressure transducers are reading atmospheric pressure. 114 □ P1, P2, and P3: Open the perimeter.

□ **OPS**: Proceed with teardown and disassembly.

115