

# Kismet Hybrid Rocket Engine Static Fire 3

Static Fire Test Operations Procedures

# **Static Fire Test Operations Procedures**

#### Contents

This document contains three procedures:

• The *Fill System Check* procedure comprises steps for validating the integrity of the system plumbing and correct operation of the test data acquisition system, using carbon dioxide.

	• The <i>Static Fire Test</i> procedure comprises steps for the engine.	operating the fill system and conduct	ing a static fire of
	Personnel Required		
	The test operations team consists of nine personnel:		
1	☐ The <b>Operations Director [OPS]</b> directs operation personnel.	ns procedures and communicates w	ith the other test
2	☐ The Primary Fill Operator [PRIMARY] operates a	all manual valves for the fill system.	
3	☐ The Secondary Fill Operator [SECONDARY] is the If PRIMARY becomes incapacitated, SECONDARY is		
4	☐ The DAQ Technician [DAQ] monitors and operate	s the test data acquisition system.	
5	☐ the <b>Control System Operator [CONTROL]</b> operativalves and engine ignition.	es the test control system, including a	ctuation of remote
6	☐ The <b>Heating Technician [HEAT]</b> operates the valve	res for the tank heating system.	
7	□ Perimeter Guard 1 [P1], Perimeter Guard 2 [P2 thorized personnel enter the testing area during test operations.		sure that no unau-
	Sign-Off		
	To be completed by all test personnel after reading and fa	amiliarization with procedures	
1	□ Operations Director [OPS]		
2	☐ Primary Fill Operator [PRIMARY]		
3	☐ Secondary Fill Operator [SECONDARY]		_
4	□ DAQ Technician [DAQ]		
5	□ Control System Operator [CONTROL]		
6	☐ Heating Technician [HEAT]		
7	□ Perimeter Guard 1 [P1]		
8	□ Perimeter Guard 2 [P2]		
9	□ Perimeter Guard 3 [P3]		

#### Prior to Start

1	$\square$ Ensure that the following procedures are complete:
2	☐ Combustion Chamber Assembly procedure
3	☐ Oxidizer Tank Assembly procedure
4	☐ Plumbing Setup procedure
5	☐ Oxidizer Tank Stand Setup procedure
6	☐ Tank Heating Setup procedure
7	$\square$ Test Stand Setup procedure
8	☐ Data Acquisition Setup procedure
9	☐ Test Control System Setup procedure
10	$\square$ Ensure that all personnel as defined above are available and have completed the sign-off.
11	$\Box$ Ensure that the following personnel have walkie-talkies and communication is functional:
12	□ OPS
13	□ SECONDARY
14	□ DAQ
15	□ <b>P1</b>
16	□ <b>P2</b>
17	□ <b>P3</b>
18	$\square$ Ensure that all spectators and test personnel are wearing safety glasses and hearing protection.
19	☐ Ensure that <b>PRIMARY</b> and <b>SECONDARY</b> are wearing face shields and have no exposed skin.
20	☐ Ensure that <b>PRIMARY</b> is wearing thermal gloves.
21	☐ Ensure that <b>OPS</b> is in possession of the system control key.

### Fill System Check Procedure

1	□ PRIMARY: Confirm that the following valves are initially closed:
2	☐ Cylinder Valve
3	☐ Remote Fill Valve
4	☐ Parallel Fill Valve
5	☐ Tank Vent Valve
6	□ Pressure Relief Valve
7	☐ Line Vent Valve
8	☐ Injector Valve
9	□ PRIMARY: Confirm that the following valves are initially open:
10	☐ Series Fill Valve
11	□ DAQ: Confirm that all pressure transducers are reading atmospheric pressure.
12	□ DAQ: Confirm that all load cells are reading the determined zero point.
13	$\square$ OPS: Confirm that all personnel in the testing area are aware of the test.
14	□ P1, P2, and P3: Close the perimeter and do not allow any further personnel to enter the testing area.
15	$\square$ SECONDARY: Confirm that no personnel are present in the testing area other than PRIMARY and SECONDARY.
16	□ PRIMARY: Remove all plastic plugs and covers from the plumbing:
17	☐ Tank Vent Valve
18	☐ Pressure Relief Valve
19	☐ Line Vent Valve
20	□ Nozzle
21	☐ PRIMARY: Remove the cap from the carbon dioxide supply cylinder.
22	$\Box$ <b>PRIMARY</b> : Connect the fill line to the supply cylinder, hand tighten, and then tighten with a wrench. Do not force the connection.
23	$\square$ <b>PRIMARY</b> : Slowly open the Cylinder Valve through $\frac{3}{4}$ of a turn.
	If leaks are observed:
24	☐ PRIMARY: Close the Cylinder Valve.
25	□ PRIMARY: Slowly open the Line Vent Valve.
26	□ PRIMARY: Slowly open the Parallel Fill Valve.
27 28	<ul> <li>DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.</li> <li>OPS: Abort test procedures and revisit plumbing setup.</li> </ul>
29	□ PRIMARY: Communicate the supply cylinder pressure as visible on the Pressure Gauge.
30	□ DAQ: Communicate the supply cylinder pressure as read by the Fill Pressure Transducer.
31	□ DAQ: Confirm that the two pressure measurements are in agreement.
32	
	□ OPS: Give the system control key to CONTROL.
33	<ul> <li>CONTROL: Engage the key switch and power on the control boxes.</li> </ul>

34	□ CONTROL: Open the Tank Vent Valve.
35	□ CONTROL: Open the Remote Fill Valve.
	• If leaks are observed:
36	□ CONTROL: Close the Remote Fill Valve.
37	☐ PRIMARY: Close the Cylinder Valve.
38	☐ PRIMARY: Slowly open the Line Vent Valve.
39	☐ PRIMARY: Slowly open the Parallel Fill Valve.
40	□ CONTROL: Open the Remote Fill Valve.
41	□ DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.
42	□ <b>OPS</b> : Abort test procedures and revisit plumbing setup.
	• If the Remove Fill Valve fails to open:
43	$\square$ OPS: Abort test procedures and revisit control system setup.
44	$\square$ DAQ: Confirm that the oxidizer tank mass is increasing.
45	□ DAQ: Confirm that the oxidizer tank pressure is increasing.
46	□ CONTROL: Close the Remote Fill Valve
47	□ CONTROL: Open the Line Vent Valve.
48	$\hfill \Box$ DAQ: Confirm that the Oxidizer Tank Pressure Transducer is reading atmospheric pressure.
49	□ PRIMARY: Close the Cylinder Valve.
50	□ CONTROL: Open the Remote Fill Valve.
51	□ DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.
52	□ PRIMARY: Disconnect the fill line from the supply cylinder.
53	□ PRIMARY: Replace the cap on the carbon dioxide supply cylinder.
54	□ <b>OPS</b> : Wait for at least 3 minutes before proceeding.
55	□ P1, P2, and P3: Open the perimeter.
56	□ <b>OPS</b> : Proceed with final setup for Static Fire Test procedure.

## Static Fire Test - Remote Control Procedure

1	☐ SECONDARY: Confirm that the ignition wires are not connected to the engine.
2	□ PRIMARY: Confirm that the following valves are initially closed:
3	☐ Cylinder Valve
4	☐ Remote Fill Valve
5	☐ Parallel Fill Valve
6	☐ Pressure Relief Valve
7	☐ Tank Vent Valve
8	☐ Line Vent Valve
9	$\square$ Injector Valve
10	□ PRIMARY: Confirm that the following valves are initially open:
11	☐ Series Fill Valve
12	□ DAQ: Confirm that all pressure transducers are reading atmospheric pressure.
13	$\square$ DAQ: Confirm that all load cells are reading the determined zero point.
14	$\square$ DAQ: Confirm that all thermistors are reading ambient temperature.
15	□ PAUSE POINT
16	□ P1, P2, and P3: Close the perimeter and do not allow any further personnel to enter the testing area.
17	□ SECONDARY: Confirm that no personnel are present in the testing area other than PRIMARY and SECONDARY.
18	☐ PRIMARY: Remove all plastic plugs and covers from the plumbing:
19	☐ Tank Vent Valve
20	☐ Pressure Relief Valve
21	☐ Line Vent Valve
22	□ Nozzle
23	$\Box$ SECONDARY: Confirm that the resistance across the ignition coils is between 2.5 $\Omega$ and 3 $\Omega$ :
24	$\square$ Primary ignition coil
25	$\square$ Secondary ignition coil
26	☐ SECONDARY: Connect the ignition connectors to the ignition box.
27	☐ PRIMARY: Remove the cap from the nitrous oxide supply cylinder.
28	$\Box$ <b>PRIMARY</b> : Connect the fill line to the supply cylinder, hand tighten, and then tighten with a wrench. Do not force the connection.
29	$\Box$ <b>PRIMARY</b> : Slowly open the Cylinder Valve through $\frac{3}{4}$ of a turn.
	If leaks are observed:
30	☐ PRIMARY: Close the Cylinder Valve.
31	□ PRIMARY: Slowly open the Parallel Fill Valve.
32	□ PRIMARY: Open the Line Vent Valve using the ropes.
33	□ DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.

34	□ <b>OPS</b> : Abort test procedures and revisit plumbing setup.
35	□ <b>PRIMARY</b> : Communicate the supply cylinder pressure as visible on the Pressure Gauge.
36	□ DAQ: Communicate the supply cylinder pressure as read by the Fill Pressure Transducer.
37	□ DAQ: Confirm that the two pressure measurements are in agreement.
38	☐ PRIMARY and SECONDARY: Retreat to the test control area, behind the blast shield.
39	□ PRIMARY: Confirm that all actuator controls are in the "off" position:
40	☐ Remote Fill Valve
41	☐ Tank Vent Valve
42	☐ Injector Valve
43	☐ Primary Ignition
44	☐ Secondary Ignition
45	□ PAUSE POINT
46	□ <b>OPS</b> : Poll the following personnel for GO/NO GO status:
47	□ <b>P1</b>
48	□ <b>P2</b>
49	□ <b>P3</b>
50	□ HEAT
51	□ DAQ
52	□ CONTROL
53	□ PRIMARY
54	□ SECONDARY
55	□ <b>OPS</b> : Give the system control key to <b>CONTROL</b> .
56	□ CONTROL: Engage the key switch and power on the control boxes.
57	□ CONTROL: Open the Tank Vent Valve.
58	□ CONTROL: Open the Remote Fill Valve.
	• If leaks are observed:
59	☐ CONTROL: Close the Remote Fill Valve.
60	□ PRIMARY: Open the Line Vent Valve using the ropes.
61	OPS: Proceed only when the oxidizer tank has fully vented.
62 63	<ul><li>PRIMARY and SECONDARY: Approach the test plumbing.</li><li>PRIMARY: Close the Cylinder Valve.</li></ul>
64	☐ CONTROL: Open the Remote Fill Valve.
65	□ DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.
66	□ <b>OPS</b> : Abort test procedures and revisit plumbing setup.
	If the Remote Fill Valve fails to open:
67	□ <b>OPS</b> : Abort test procedures and revisit control system setup.
68	☐ SECONDARY: Proceed only when a white plume is visible from the Tank Vent Valve.
69	□ CONTROL: Close the Tank Vent Valve.

70	□ CONTROL: Close the Remote Fill Valve.
	If the Remote Fill Valve fails to close:
71	☐ PRIMARY and SECONDARY: Approach the test plumbing.
72	☐ PRIMARY: Close the Series Fill Valve.
73	☐ PRIMARY and SECONDARY: Retreat to the test control area, behind the blast shield.
74	☐ <b>HEAT</b> : Open the Tank Heating Valve.
75	□ DAQ: Proceed only when the oxidizer tank pressure is at least 800 psi.
	• If the oxidizer tank pressure does not reach 800 psi:
76	☐ <b>HEAT</b> : Close the Tank Heating Valve.
77	☐ PRIMARY: Open the Line Vent Valve using the ropes.
78	☐ <b>OPS</b> : Proceed only when the oxidizer tank has fully vented.
79	☐ PRIMARY and SECONDARY: Approach the test plumbing.
80	□ PRIMARY: Close the Cylinder Valve.
81	□ CONTROL: Open the Tank Vent Valve.
82	□ CONTROL: Open the Remote Fill Valve.
83 84	<ul> <li>DAQ: Confirm that the Oxidizer Tank Pressure Transducer is reading atmospheric pressure.</li> <li>OPS: Abort test procedures and revisit water jacket setup.</li> </ul>
85	☐ HEAT: Close the Tank Heating Valve.
86	□ PAUSE POINT
87	□ CONTROL: Perform engine startup procedure:
88	$\square$ Arm the Primary Ignition switch.
89	$\square$ Hold down the Fire button until black smoke is observed.
	<ul> <li>In the event of a failed ignition (smoke not observed within 1 minute):</li> </ul>
90	☐ CONTROL: Disarm the Primary Ignition switch.
91	□ CONTROL: Arm the Secondary Ignition switch.
92	□ OPS: Revisit ignition procedure.
93	<ul> <li>In the event of a second failed ignition (smoke not observed within 1 minute):</li> <li>CONTROL: Disarm the Secondary Ignition switch.</li> </ul>
94	□ PRIMARY: Open the Line Vent Valve using the ropes.
95	□ OPS: Proceed only when the oxidizer tank has fully vented.
96	□ PRIMARY and SECONDARY: Approach the test plumbing.
97	□ PRIMARY: Close the Cylinder Valve.
98	□ CONTROL: Open the Remote Fill Valve.
99	☐ CONTROL: Open the Tank Vent Valve.
100	$\qed$ DAQ: Confirm that the Oxidizer Tank Pressure Transducer is reading atmospheric pressure.
101	□ <b>OPS</b> : Abort test procedures and proceed to teardown.
102	☐ CONTROL: Start the engine by opening the Injector Valve.
103	☐ <b>ALL</b> : Observe the plume:
	<ul> <li>If any unexpected events occur during the engine firing:</li> </ul>
104	□ PRIMARY: Open the Line Vent Valve using the ropes.
105	OPS: Wait for 3 seconds.
106	☐ CONTROL: Close the Injector Valve.

107	□ PAUSE POINT
108	$\square$ <b>OPS</b> : Wait for at least 3 minutes before proceeding.
109	$\square$ DAQ: Confirm that the Oxidizer Tank Pressure Transducer is reading atmospheric pressure.
110	□ CONTROL: Open the Tank Vent Valve.
111	□ PRIMARY and SECONDARY: Approach the test plumbing.
112	□ PRIMARY: Close the Cylinder Valve.
113	□ CONTROL: Open the Remote Fill Valve.
114	$\square$ DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.
115	□ PRIMARY: Disconnect the fill line from the supply cylinder.
116	□ PRIMARY: Replace the cap on the nitrous oxide supply cylinder.
117	□ <b>OPS</b> : Wait for at least 3 minutes before proceeding.
118	□ P1, P2, and P3: Open the perimeter.
119	$\Box$ DAQ: Continue to monitor thermistor readings and inform OPS if the combustion chamber temperature exceeds 190 $^{\circ}\text{C}.$
120	□ <b>OPS</b> : Proceed with teardown and disassembly.