

## Unnamed Liquid Rocket Engine Static Fire 1

Static Fire Test Operations Procedures

## **Static Fire Test Operations Procedures**

Cor	ntents
This	s document contains one procedure:
•	• The Static Fire Test procedure comprises steps for operating the fill system and conducting a static fire o the engine.
Per	sonnel Required
The	test operations team consists of nine personnel:
	The <b>Operations Director [OPS]</b> directs operations procedures and communicates with the other testonnel.
	The Primary Fill Operator [PRIMARY] operates all manual valves for the fill system.
	The <b>Secondary Fill Operator [SECONDARY]</b> is the backup for <b>PRIMARY</b> , and communicates with OPS <b>RIMARY</b> becomes incapacitated, <b>SECONDARY</b> is responsible for removing them from danger.
	The DAQ Technician [DAQ] monitors and operates the test data acquisition system.
	The <b>Control System Operator [CONTROL]</b> operates the test control system, including actuation of ote valves and engine ignition.
Sig	n-Off
То	be completed by all test personnel after reading and familiarization with procedures
	Operations Director [OPS]
	Primary Fill Operator [PRIMARY]
	Secondary Fill Operator [SECONDARY]
	DAQ Technician [DAQ]
	Control System Operator [CONTROL]

## Prior to Start

11

1	$\square$ Ensure that all personnel as defined above are available and have completed the sign-off.
2	$\hfill\Box$ Ensure that the following personnel have walkie-talkies and communication is functional:
3	□ OPS
4	□ SECONDARY
5	□ DAQ
6	□ CONTROL
7	$\square$ Ensure that all spectators and test personnel are wearing safety glasses and hearing protection.
8	☐ Ensure that <b>PRIMARY</b> and <b>SECONDARY</b> are wearing face shields and have no exposed skin.
9	☐ Ensure that <b>PRIMARY</b> is wearing thermal gloves.
10	☐ Ensure that <b>SECONDARY</b> is in possession of a multimeter.

 $\hfill\Box$  Ensure that  $\ensuremath{\mathsf{OPS}}$  is in possession of the system control key.

## Static Fire Test - Remote Control Procedure

1	☐ <b>SECONDARY</b> : Confirm that the ignition wires are not connected to the engine.
2	□ PRIMARY: Confirm that the following valves are initially closed:
3	☐ SC-1 (Oxidizer Supply Valve)
4	☐ TK-1 (Pressurant Supply Valve)
5	☐ BA-1 (Oxidizer Pressurant Shutoff Valve)
6	□ BA-2 (Fuel Pressurant Shutoff Valve)
7	☐ BA-3 (Oxidizer Parallel Fill Valve)
8	☐ BA-5 (Oxidizer Fill Line Vent Valve)
9	$\square$ BA-8 (Oxidizer Tank Dump Valve)
10	□ BA-9 (Fuel Tank Vent Valve)
11	□ BA-10 (Pressurant Line Vent Valve)
12	☐ MV-1 (Oxidizer Motorized Fill Valve)
13	□ MV-2 (Pressurant Remote Valve)
14	□ MV-3 (Oxidizer Motorized Vent Valve)
15	□ MV-4 (Fuel Injector Valve)
16	□ IJ-1 (Oxidizer Injector Valve)
17	□ PRIMARY: Confirm that the following valves are initially open:
18	☐ BA-4 (Oxidizer Series Fill Valve)
19	☐ BA-6 (Oxidizer Shutoff Valve)
20	$\square$ BA-7 (Fuel Shutoff Valve)
21	□ PRIMARY: Confirm that CV-1 is adjusted to the lowest pressure setting.
22	$\square$ DAQ: Confirm that all pressure transducers are reading atmospheric pressure.
23	$\square$ DAQ: Confirm that all load cells are reading the determined zero point.
24	$\square$ DAQ: Confirm that all thermistors are reading ambient temperature.
25	□ PAUSE POINT
26	□ SECONDARY: Confirm that no personnel are present in the testing area other than PRIMARY and SECONDARY.
27	☐ PRIMARY: Remove all plastic plugs and covers from the plumbing:
28	☐ Oxidizer Tank Remote Vent Line
29	☐ Oxidizer Tank Dump Line
30	☐ Oxidizer Fill Vent Line
31	☐ Fuel Tank Vent Line
32	□ Pressurant Vent Line
33	□ Nozzle
34	□ PRIMARY: Remove the cap from the pressurant supply cylinder.
35	$\square$ <b>PRIMARY</b> : Connect the pressurant line to the cylinder, hand tighten, and tighten with a wrench.
36	☐ PRIMARY: Slowly open TK-1, watching for leaks.

	If leaks are observed:
37	□ PRIMARY: Close TK-1.
38	☐ PRIMARY: Adjust CV-1 until PI-1 shows at least 100 psi.
39	☐ PRIMARY: Slowly open BA-10 to vent the pressurant lines.
40	□ PRIMARY: Close BA-10.
41	□ PRIMARY: Inspect the plumbing connections at the pressurant lines.
42	☐ PRIMARY: Adjust CV-1 until PI-1 shows 600 psi.
	• If leaks are observed:
43	□ PRIMARY: Close TK-1.
44	☐ PRIMARY: Slowly open BA-10 to vent the pressurant lines.
45	□ PRIMARY: Close BA-10.
46	□ PRIMARY: Inspect the plumbing connections at the pressurant lines.
47	□ DAQ: Confirm that PT-5 reads 600 psi.
48	□ PRIMARY: Open BA-1.
49	□ PRIMARY: Open BA-2.
50	□ DAQ: Confirm that PT-1 and PT-3 read atmospheric pressure.
51	$\Box$ <b>SECONDARY</b> : Confirm that the resistance across the ignition coils is between 2.5 $\Omega$ and 3 $\Omega$ :
52	$\Box$ Primary ignition coil
53	$\square$ Secondary ignition coil
54	☐ <b>SECONDARY</b> : Connect the ignition connectors to the ignition box.
55	☐ PRIMARY: Remove the cap from the nitrous oxide supply cylinder.
56	$\square$ <b>PRIMARY</b> : Connect the fill line to the supply cylinder, hand tighten, and then tighten with a wrench. Do not force the connection.
57	□ PRIMARY: Slowly open SC-1.
	• If leaks are observed:
58	□ PRIMARY: Close SC-1.
59	☐ PRIMARY: Open BA-8.
60	☐ PRIMARY: Slowly open BA-3.
61	□ DAQ: Confirm that PT-2 is reading atmospheric pressure.
62	□ PRIMARY: Inspect the plumbing connections at the oxidizer fill lines.
63	□ PRIMARY: Communicate the supply cylinder pressure as visible on the Pressure Gauge.
64	$\square$ DAQ: Communicate the supply cylinder pressure as read by the Fill Pressure Transducer.
65	$\square$ DAQ: Confirm that the two pressure measurements are in agreement.
66	□ PRIMARY and SECONDARY: Retreat to the test control area.
67	□ <b>CONTROL</b> : Confirm that all actuator controls are in the "off" position:
68	☐ Motorized Fill Valve
69	☐ Motorized Vent Valve
70	☐ Pressurant Remote Valve

71	☐ Injector Valve
72	☐ Primary Ignition
73	☐ Secondary Ignition
74	□ PAUSE POINT
75	□ <b>OPS</b> : Give the system control key to <b>CONTROL</b> .
76	□ CONTROL: Engage the key switch and power on the control boxes.
77	□ CONTROL: Open the Motorized Vent Valve.
78	□ CONTROL: Open the Motorized Fill Valve.
	If leaks are observed:
79	☐ CONTROL: Close the Motorized Fill Valve.
80	□ <b>OPS</b> : Proceed only when the oxidizer tank has fully vented.
81	☐ PRIMARY and SECONDARY: Approach the test plumbing.
82	□ PRIMARY: Close SC-1.
83	☐ CONTROL: Open the Motorized Fill Valve.
84	□ DAQ: Confirm that PT-1 and PT-3 are reading atmospheric pressure.
85	☐ <b>OPS</b> : Abort test procedures and revisit plumbing setup.
	<ul> <li>If the Remote Fill Valve fails to open:</li> </ul>
86	☐ <b>OPS</b> : Abort test procedures and revisit control system setup.
87	$\square$ DAQ: Proceed only when the oxidizer tank mass reaches a steady state.
88	□ CONTROL: Close the Motorized Vent Valve.
89	□ CONTROL: Close the Motorized Fill Valve.
90	□ PAUSE POINT
91	□ CONTROL: Open the Pressurant Remote Valve.
92	□ DAQ: Proceed only when PT-1 and PT-3 read 600 psi.
93	□ CONTROL: Close the Pressurant Remote Valve.
94	□ PAUSE POINT
95	$\square$ <b>OPS</b> : Poll the following personnel for GO/NO GO status:
96	□ PRIMARY
97	□ SECONDARY
98	□ DAQ
99	□ CONTROL
100	□ CONTROL: Perform engine startup procedure:
101	$\square$ Arm the Primary Ignition switch.
102	$\hfill \square$ Hold down the Fire button until the Primary ignition current drops to 0 A.
	ullet In the event of a failed ignition (current drop not observed within 1 minute):
103	☐ <b>CONTROL</b> : Disarm the Primary Ignition switch.
104	☐ CONTROL: Arm the Secondary Ignition switch.
105	☐ <b>OPS</b> : Revisit ignition procedure.

106	• In the event of a second failed ignition (current drop not observed within 1 minute):
<ul><li>106</li><li>107</li></ul>	<ul><li>CONTROL: Disarm the Secondary Ignition switch.</li><li>CONTROL: Open the Motorized Vent Valve to vent the oxidizer tank.</li></ul>
108	□ OPS: Proceed only when the oxidizer tank has fully vented.
109	□ DAQ: Confirm that PT-1 is reading atmospheric pressure.
110	□ PRIMARY and SECONDARY: Approach the test plumbing.
111	☐ PRIMARY: Open BA-9 using the ropes to depressurize the fuel tank.
112	□ DAQ: Confirm that PT-3 is reading atmospheric pressure.
113	□ PRIMARY: Close SC-1.
114	☐ CONTROL: Open the Motorized Fill Valve to vent the oxidizer supply lines.
115	□ DAQ: Confirm that PT-2 is reading atmospheric pressure.
116	<ul><li>□ PRIMARY: Close TK-1.</li><li>□ PRIMARY: Slowly open BA-10 to vent the pressurant lines.</li></ul>
<ul><li>117</li><li>118</li></ul>	□ DAQ: Confirm that PT-5 is reading atmospheric pressure.
119	□ OPS: Abort test procedures and proceed to teardown.
120	□ CONTROL: Start the engine by opening the Injector Valve.
121	□ <b>ALL</b> : Observe the plume.
122	□ PAUSE POINT
123	□ <b>OPS</b> : Wait for at least 3 minutes before proceeding.
124	□ DAQ: Confirm that PT-1 and PT-3 are reading atmospheric pressure.
125	□ CONTROL: Open MV-3.
126	□ PRIMARY and SECONDARY: Approach the test plumbing.
127	□ PRIMARY: Close SC-1.
128	☐ CONTROL: Open the Motorized Fill Valve to vent the oxidizer supply lines.
129	□ DAQ: Confirm that PT-2 is reading atmospheric pressure.
130	□ PRIMARY: Close TK-1.
131	☐ PRIMARY: Slowly open BA-10 to vent the pressurant lines.
132	□ DAQ: Confirm that PT-5 is reading atmospheric pressure.
133	☐ PRIMARY: Disconnect the fill line from the oxidizer supply cylinder.
134	☐ PRIMARY: Replace the cap on the oxidizer supply cylinder.
135	☐ PRIMARY: Disconnect the fill line from the pressurant supply cylinder.
136	☐ PRIMARY: Replace the cap on the pressurant supply cylinder.
137	□ <b>OPS</b> : Wait for at least 3 minutes before proceeding.
138	$\Box$ DAQ: Continue to monitor thermistor readings and inform OPS if the combustion chamber temperature exceeds 190 $^{\circ}\text{C}.$
139	□ <b>OPS</b> : Proceed with teardown and disassembly.