

Kismet Hybrid Rocket Engine Cold Flow 3

Cold Flow Test Operations Procedures

Cold Flow Test Operations Procedures

☐ Control System Operator [CONTROL]

☐ Heating Technician [HEAT]

□ Perimeter Guard 1 [P1]

☐ Perimeter Guard 2 [P2]

□ Perimeter Guard 3 [P3]

5

6

7

8

Contents
This document contains the following procedure:
• The <i>Cold Flow Test</i> procedure comprises steps for conducting a carbon dioxide test of the engine and fill system using the electrical control system and motorized ball valves.
Personnel Required
The test operations team consists of nine personnel:
\Box The Operations Director [OPS] directs operations procedures and communicates with the other test personnel.
\Box The Primary Fill Operator [PRIMARY] is the main system operator. PRIMARY operates all manual valves as well as the test control system.
☐ The Secondary Fill Operator [SECONDARY] is the backup for PRIMARY , and communicates with OPS. If PRIMARY becomes incapacitated, SECONDARY is responsible for removing them from danger.
$\ \square$ The DAQ Technician [DAQ] monitors and operates the test data acquisition system.
☐ the Control System Operator [CONTROL] operates the test control system, including actuation of remote valves.
\Box The Heating Technician [HEAT] operates the valves for the tank heating system.
□ Perimeter Guard 1 [P1], Perimeter Guard 2 [P2], and Perimeter Guard 3 [P3] ensure that no unauthorized personnel enter the testing area during test operations.
Sign-Off
To be completed by all test personnel after reading and familiarization with procedures
□ Operations Director [OPS]
□ Primary Fill Operator [PRIMARY]
□ Secondary Fill Operator [SECONDARY]
□ DAQ Technician [DAQ]

Prior to Start

1	\square Ensure that the following procedures are complete:
2	☐ Oxidizer Tank Assembly procedure
3	☐ Plumbing Setup procedure
4	☐ Oxidizer Tank Stand Setup procedure
5	\square Tank Heating Setup procedure
6	\square Test Stand Setup procedure
7	\square Data Acquisition Setup procedure
8	☐ Test Control System Setup procedure
9	\Box Ensure that all technicians as defined above are available and have completed the sign-off.
10	\square Ensure that all spectators and test personnel are wearing safety glasses.
11	☐ Ensure that PRIMARY and SECONDARY are wearing face shields and have no exposed skin.
12	☐ Ensure that PRIMARY is wearing thermal gloves.
13	☐ Ensure that OPS is in possession of the system control key.

Cold Flow Test Procedure

1	□ PRIMARY: Confirm that the following valves are initially closed:
2	☐ Cylinder Valve
3	☐ Remote Fill Valve
4	☐ Parallel Fill Valve
5	☐ Motorized Vent Valve
6	☐ Line Vent Valve
7	☐ Injector Valve
8	□ PRIMARY: Confirm that the following valves are initially open:
9	☐ Series Fill Valve
LO	☐ Linear Actuator Vent Valve
11	□ DAQ: Confirm that all pressure transducers are reading atmospheric pressure.
12	□ DAQ: Confirm that all load cells are reading the determined zero point.
13	□ PAUSE POINT
L4	□ P1, P2, and P3: Close the perimeter and do not allow any further personnel to enter the testing area.
15	□ SECONDARY: Confirm that no personnel are present in the testing area other than PRIMARY and SECONDARY.
16	☐ PRIMARY: Remove the cap from the carbon dioxide supply cylinder.
17	\Box PRIMARY : Connect the fill line to the supply cylinder, hand tighten, and then tighten with a wrench. Do not force the connection.
18	\Box PRIMARY : Slowly open the Cylinder Valve through $\frac{3}{4}$ of a turn.
	If leaks are observed:
19	☐ PRIMARY: Close the Cylinder Valve.
20	□ PRIMARY: Open the Line Vent Valve.
21 22	 PRIMARY: Slowly open the Parallel Fill Valve. DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.
23	□ OPS: Abort test procedures and revisit plumbing setup.
24	☐ PRIMARY: Communicate the supply cylinder pressure as visible on the Pressure Gauge.
25	□ DAQ: Communicate the supply cylinder pressure as read by the Fill Pressure Transducer.
26	□ DAQ: Confirm that the two pressure measurements are in agreement.
27	☐ PRIMARY and SECONDARY: Retreat to the test control area, behind the blast shield.
28	□ PRIMARY: Perform the following control system checks:
29	☐ Confirm that all actuator controls are in the "closed" position:
30	☐ Remote Fill Valve
31	☐ Motorized Vent Valve
32	☐ Injector Valve
33	□ PAUSE POINT

34	□ OPS : Poll the following personnel for GO/NO GO status:
35	□ HEAT
36	□ CONTROL
37	□ DAQ
38	□ PRIMARY
39	□ SECONDARY
40	□ OPS : Give the system control key to CONTROL .
41	□ CONTROL: Engage the key switch and power on the control boxes.
42	□ CONTROL: Open the Motorized Vent Valve.
43	□ CONTROL: Open the Remote Fill Valve.
	• If leaks are observed:
44	☐ CONTROL: Close the Remote Fill Valve.
45	☐ CONTROL: Open the Injector Valve.
46	□ OPS : Proceed only when the oxidizer tank has fully vented.
47	☐ PRIMARY and SECONDARY: Approach the test plumbing.
48	☐ PRIMARY: Close the Cylinder Valve.
49	□ CONTROL: Open the Remote Fill Valve.
50	□ DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.
51	□ OPS: Abort test procedures and revisit plumbing setup.
	If the Remote Fill Valve fails to open:
52	☐ OPS : Abort test procedures and revisit control system setup.
53	□ OPS : Proceed only when a white plume is visible from the vent plug.
54	□ CONTROL: Close the Motorized Vent Valve.
55	□ CONTROL: Close the Remote Fill Valve.
	If the Remote Fill Valve fails to close:
56	☐ PRIMARY and SECONDARY: Approach the test plumbing.
57	☐ PRIMARY: Close the Series Fill Valve.
58	□ PRIMARY and SECONDARY: Retreat to the test control area.
59	☐ HEAT : Open the Tank Heating Valve.
60	□ DAQ: Proceed only when the oxidizer tank pressure is at least 750 psi.
	• If the oxidizer tank pressure does not reach 750 psi:
61	☐ HEAT : Close the Tank Heating Valve.
62	☐ CONTROL: Open the Injector Valve.
63	□ OPS : Proceed only when the oxidizer tank has fully vented.
64	☐ PRIMARY and SECONDARY: Approach the test plumbing.
65	□ PRIMARY: Close the Cylinder Valve.
66	□ CONTROL: Open the Remote Fill Valve.
67	□ DAQ: Confirm that the Oxidizer Tank Pressure Transducer is reading atmospheric pressure.
68	□ OPS: Abort test procedures and revisit plumbing setup.
69	☐ HEAT : Close the Tank Heating Valve.

70	□ CONTROL: Open the Motorized Vent Valve.
71	□ CONTROL: Close the Linear Actuator Vent Valve.
72 73	 If leaks are observed or the Linear Actuator Vent Valve fails to close: CONTROL: Close the Motorized Vent Valve. OPS: Proceed with the cold flow test.
	Otherwise:
74 75 76	 □ CONTROL: Open the Linear Actuator Vent Valve. □ OPS: Proceed with the cold flow test. □ CONTROL: Close the Motorized Vent Valve.
77	□ PAUSE POINT
78	□ CONTROL: Conduct the cold flow test by opening the Injector Valve.
79	□ PAUSE POINT
80	$\hfill \Box$ DAQ: Confirm that the Oxidizer Tank Pressure Transducer is reading atmospheric pressure.
81	☐ PRIMARY: Open the Line Vent Valve using the ropes.
82	□ CONTROL: Open the Motorized Vent Valve.
83	□ OPS : Proceed only when the oxidizer tank has fully vented.
84	☐ PRIMARY and SECONDARY: Approach the test plumbing.
85	□ PRIMARY: Close the Cylinder Valve.
86	□ CONTROL: Open the Remote Fill Valve.
87	☐ PRIMARY: Slowly open the Parallel Fill Valve.
88	☐ PRIMARY: Disconnect the fill line from the supply cylinder.
89	☐ PRIMARY: Replace the cap on the carbon dioxide supply cylinder.
90	\square DAQ: Confirm that the Fill Pressure Transducer is reading atmospheric pressure.
91	□ OPS : Wait for at least 3 minutes before proceeding.
92	□ P1, P2, and P3: Open the perimeter.
93	□ OPS : Proceed with teardown and disassembly.